

FIBERGLASS SIDELITE PANEL · FLUSH GLAZED · HURRICANE IMPACT RATED (WIND-BORNE DEBRIS)

Scan to view this sidelite
online: current options,
pricing and install guides




2-Lite Grilles Between Glass Craftsman Top Lite Sidelite

14" x 96" nominal (1/2 x 8/0) · Actual sidelite 13-7/8" x 95" x 1-3/4"

FIG. 1 ELEVATION AND EDGE VIEW

Exterior face. To scale; actual inches.



DIMENSIONS


Nominal size	14" x 96" (1/2 x 8/0)
Actual sidelite	13-7/8" W x 95" H x 1-3/4" thick
Stiles	2-13/16" each side, to the lite field
Rails	Top 5-1/8" · bottom 8-3/4"
Lite opening	8-1/4" x 20-1/2"
Lower panel	8-1/4" x 54-5/8"
In a unit	Pairs with 97-3/4" leg jambs (inswing or saddle sill) or 96-3/4" (bumper sill); same height as the door

CONSTRUCTION

Build	Impact-rated build, wind-borne debris approved
Stiles	LVL stiles with composite PVC edge caps
Rails	Composite top and bottom rails
Core	Foamed-in-place polyurethane, 2.2 lb/cu ft
Skins	Compression-molded fiberglass
Texture	Tan Rift Cut woodgrain or White Satin Smooth (paint grade)
Panel profile	Shaker: 105° bevel to a recessed flat, 3/8" deep (Fig. 2)
Edges	Square edge; fixed panel, no hinge or lock prep

FIG. 2 SHAKER EMBOSSMENT PROFILE

105° bevel from the stile face to a recessed flat, 3/8" deep: a crisp, minimal shaker reveal.



PERFORMANCE

U-factor / SHGC	0.23 / 0.04 (NFRC 100 / 200)
ENERGY STAR 7.0	All U.S. climate zones
Impact rating	Large and small missile; wind-borne debris regions, not the HVHZ
Design pressure	Inswing +40 / -45 psf; outswing ±50 psf
Fire rating	Not fire rated
Glass	25,000 slam cycles; IG certified to ASTM E2190

Thermal: NFRC calculated ratings, flush glazed impact Low-E glass with grilles, under 411 sq in glass class. Impact and DP per Florida approval FL47925; not for Miami-Dade or Broward (HVHZ). Wind Zone 4 also requires an approved impact protective system.


GLASS

Glass size	9" x 21-1/4"; daylight 8" x 20-1/4"
Unit	Flush glazed, no frame. Impact-rated insulated glass with a laminated pane
Design	2-lite grid (1 x 2) of white 5/8" or 7/8" grilles sealed between the panes. Privacy: none

CONSTRUCTION AND INSTALLATION

FIG. 3 CONSTRUCTION DETAIL

Cutaway at the top corner



- ① Composite PVC edge cap
- ② LVL stile
- ③ Composite top and bottom rails
- ④ Glass, flush glazed into the panel

INSTALLATION

Sidelite panels are fixed and have no hinge or lock prep. Install alongside a door slab of the same height, assembled into one frame with 97-3/4" leg jambs (inswing or saddle sill). For rated performance, the complete unit must be built and installed per the product approval. Step-by-step guides are on the product page (scan the QR code).

FINISHING

Rift Cut woodgrain: gel stain made for fiberglass, then a polyurethane topcoat with UV inhibitor (or paint over a bonding primer). **Satin Smooth:** bonding primer, then premium exterior acrylic latex paint. **Finish all six sides** promptly after delivery. Avoid very dark colors in direct sun.

TRIMMING

This sidelite is not a trimmable model. If needed, it can be trimmed up to **1/2" off the bottom only**; seal the cut edge. **Do not trim the top or sides.** Trimming a product that is not sold as trimmable voids the warranty, and modified products cannot be returned.

PEASE DOORS 20-YEAR LIMITED WARRANTY

Covers the sidelite panel and its glass against defects in material and workmanship that make the product unfit for normal use. Valid for products purchased and installed in the USA with original proof of purchase. Requires proper storage, finishing and installation. Not valid when installed behind a storm door.

Year	1	2-3	4-6	7	8	9	10	11-20
Coverage	100%	90%	80%	70%	60%	50%	40%	30%

*Share of replacement cost covered, by year after purchase.
Full terms and claims: [peasedoors.com/pages/warranty](https://www.peasedoors.com/pages/warranty)*